



Date: 2019

Project Description: Modular Chilled Water Plant to cool and support buildings in downtown Austin

Owner: Austin Energy

GC/CM: SpawGlass

Facility Size: Roof of Austin Convention Center

Scope Performed: Took Owner's design criteria and developed a chilled water utility solution with 3,000 tons of cooling. Modular chiller plant included chillers, condenser water system, cooling towers, pumps, and all associated power distribution and controls.

Delivery Method: Design-Build

Contract Value: \$4.5 Million

